456

LOST—

Right half of Currency Note.

No.	*Date.*	*Circle.*	*Value.*	*Owner.*
13252	3rd July 1886.	Madras.	Rs. 100.	Mysore Narasanmaiya, living at Holé-Narsipur, who offers to pay Rs. 5 to the individual who may give information leading to its detection.

BANGALORE DIVISION.

ADVERTISEMENT.

The 7th November 1887.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 15th November 1887, for restoring the Virupakshipura Tank, Closepet Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1888.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 12 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government promissory notes as earnest money and be superscribed "Tender for restoring the Virupakshipura Tank, Closepet Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Bill of quantities for restoring the Virupakshipura Tank, Closepet Taluk.

Items of Work.	Per	Quantity.	Rate.	Cost.	Total
Earthwork including consolidation ..	C. Yd.	33,652			
Rebuilding old stone revetment ..	do	7,326			
New stone revetment ..	do	4,579			

T. INMAN,
Executive Engineer.

TUMKUR DIVISION.

ADVERTISEMENTS.

The 25th October 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 20th November 1887, for restoring the Gurgadahalli Tank, Registered No. 70, Tiptur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1888.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Tumkur between the hours of 1 to 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes as earnest money, and be superscribed "Tender for restoring the Gurgadahalli Tank;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate Bill.

Detailed abstract estimate of restoring Gurgadahalli Tank, Registered No. 70, Tiptur Taluk.

Items of Work.	Per	Quantity.	Rate.	Cost.
Bund.				
Earthwork	C. Yd.	19,769		
New stone work	do	2,432		
Old stone work	do	953		
Grade stones	..	42		
B. M. Stones	..	2		
Total...				
Sluices.				
No. I Sluice—Cutting and clearing .	L. S.	30		
No. II Sluice—Earthwork .	C. Yd.	400		
Brick in chunam	C. Ft.	591		
Concrete	do	173		
Plastering	Sq.	2·78		
Covering slabs	S. Ft.	117		
Front and orifice stones .. .	L. S.	3		
Gibbet stones	do	15		
Total...				
Waste Weir.				
Excavation	C. Yd.	3,706		
Brick in chunam	C. Ft.	2,151		
Plastering	Sq.	5·76		
Covering slabs	S. Ft.	291		
New stone work	C. Yd.	487		
Total...				

458.

The 28th October 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 20th November 1887, for restoring the Ponnasandra Tank, Registered No. 276, Pavagada Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1888.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Tumkur between the hours of 1 to 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring the Ponnasandra Tank :" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detailed abstract estimate of the probable cost of restoring Ponnasandra Tank, Registered No. 276, Pavagada Taluk.

Items of Work.	Per	Quantity.	Rate.	Cost.
Bund.				
Earthwork	C. Yd.	27,245		
Old stone work	do	2,976		
New stone work	do	3,358		
Grade stones	Each.	52		
B. M. Stones	do	2		
Sluice No. I.				
Repairs	L. S.	40		
Sluice No. II.				
Dismantling and removing old sluice ..	L. S.	15		
Brick in surki mortar	C. Ft.	679		
Plastering	Sq.	5·00		
Slab stones	L. S.	15		
Left Waste Weir.				
Cutting and clearing lower and upper approaches.	L. S.	150		
Right Waste Weir.				
Excavation	C. Yd.	160		
Brick in chunam	C. Ft.	1,774		
Plastering	Sq.	6·00		
Slab stones	S. Ft.	113		
Old stone work	C. Yd.	152		
New stone work	do	208		

C. T. DALAL,
Executive Engineer.